



NOTES: ALL AIR VALVES SHALL BE INSTALLED VERTICALLY PLUMB CONTRACTOR TO MAINTAIN POSITIVE SLOPE ON FORCE MAIN TO NEW AIR/VAC VALVE

DIRECT BURY TRACER WIRE W/ GREASE FILLED NUTS AT SPLICES

AIR VAC VALVE

N.T.S.

